

10-7 15-195-21021-00-00

4-060444

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-195-21,021

NW NE SE /4 SEC. 04, 12 S, 21 W  
2310 feet from S section line  
990 feet from E section line

Operator license# 5238 Lease Walz "F" well # 2

Operator: Petroleum, Inc. County Trego 131.07

Address: 301 N. Main Well total depth 4033 feet  
Suite 900 Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 755 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Co Tools License# \_\_\_\_\_

Address: \_\_\_\_\_

Company to plug at: Hour: 12:15P.M Day: 7 Month: October Year: 93

Plugging proposal received from: Terry Naylor

Company: Petroleum, Inc. Phone: 316-291-8200

Were: Order 300 sxs. 60/40 posmix - 10% gel - 8 sxs. gel and hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 1:45P.M., Day: 7, Month: October, Year: 93

Actual plugging report: 8 5/8" to 755'. 5 1/2" to 4032'. Perforate at  
960' - 1820' - 2470'. Fluid level at 3700'. Tied onto annulus and  
pumped 50 sxs. cement. Max. 700#. S.I.P. 500#. Tied onto casing.  
Pumped 25 sxs. cement with 200# hulls, followed by 8 sxs. gel in  
24 bbls. fresh water followed by 250 sxs. cement with 100# hulls.  
Max. 500#. S.I.P. 500#.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: \_\_\_\_\_ GL

I did  did not  observe the plugging.

*[Signature]*  
STATE CORPORATION COMMISSION

**INVOICED**  
DATE OCT 21 1993  
INV. NO. 39014  
10-7

*DA* (agent)  
**RECEIVED**  
OCT 18 1993  
Form CP-2/3 10-18-1993  
CONSERVATION DIVISION  
Wichita, Kansas