

4-071120

9-22 15-195-21626-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-195-21,626

SE SE NW /4 SEC. 04, 12 S, 21 W
2970 feet from S section line
2970 feet from E section line

Operator license# 5131

Lease J.D. Deutscher well # 1

Operator: Thunderbird Drilling, Inc.

County Trego

Address: P.O. Box 97
Ellinwood, Kansas 67526
Maynard Weber

Well total depth 4070 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 256 feet

132.27

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 22 Month: September Year: 94

Plugging proposal received from: Claud Blakele

Company: Thunderbird Drilling, Inc. Phone: 316-564-2577

Were: 8 5/8" - 256' S.P. cwc. w/175 sxs. cmt. 4 1/2" csq. set @ 4070'
w/170 sxs. cmt. D.V. tool at 1770' cwc. w/460 sxs. cmt. Csq. good.
Perf. 3946' - 3951'. Proposal 175 sxs. 60/40 pozmix - 10% gel and 10 sxs
Bentonite gel and 3 sxs. hulls. Pump in with pump truck. Pump in 4 1/2"
casing and 4 1/2" x 8 5/8" annulus with cement from top to bottom with
a 10 sxs. gel spacer and shut in under pressure.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 1:30P.M., Day: 22, Month: September, Year: 94

Actual plugging report: Thunderbird Drilling ordered 175 sxs. 60/40
pozmix - 10% gel and 10 sxs. Bentonite gel and 3 sxs. cotton seed hulls.
Pumped in with pump truck.

- 1) Pumped in 4 1/2" csq. w/25 sxs. cmt. w/2 sxs. hulls mixed in.
- 2) Followed with 10 sxs. Bentonite gel.
- 3) Followed with 125 sxs. cmt. Max. pressure 400# P.S.I. Shut in at
100# P.S.I.
- 4) Squeezed 4 1/2" x 8 5/8" annulus - did not take cement. Max. pressure
500# P.S.I. Shut in at 500# P.S.I.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , RECEIVED
Plugged through TUBING , CASING . Elevation: STAGI CORPORATION-COMMISSION

I did did not observe the plugging.

INVOICED

Stephen Schmitt
(agent)
OCT 05 1994
10-5-1994
CONSERVATION DIVISION
WICHITA, KANSAS
Form CP-2/3

DATE 10-10-94
INV. NO. 41388