

4-17 / 15-195-21599-00-00 <sup>237</sup> R

6 031347

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION & PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- \_\_\_\_\_  
NW SE SW \_\_\_\_\_, SEC. 4 \_\_\_\_\_, T 12 S, R 21 W/E  
990 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050  
Operator: Kelso Csg Pulling Inc.  
Name & Address: Box 347  
Chase, Ks. 67202

Lease Name B.K. DeucherWell # 1  
County Trego 133.25  
Well Total Depth 4100 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 326

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_  
Kelso

Plugging Contractor \_\_\_\_\_ License Number 6050  
Address Chase, Ks.

Company to plug at: Hour: AM Day: 17 Month: April Year: 19 90

Plugging proposal received from Millard Kelso  
(company name) Kelso (phone) \_\_\_\_\_

were: 8 5/8 set at 326 w/200 sks. 4 1/2 set at 4099 w/175 sks. Perf 3530.

PBTD 4068. Order 225 sks 65/35 poz 10% gel 2% dicel 500# hulls.

Allied Cement Co. Wellbrock water trucks.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:40AM Day: 17 Month: April Year: 19 90

ACTUAL PLUGGING REPORT Sand bottom to 3480 w/4 sks common cement on sand w/bailer.

One shot recovered 2630' of 4 1/2 casing. Sq 8 5/8 w/225 sks cmt blend to 500# hulls mixed into max psi 1100#. Close in psi 200#. Plug completed.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED MAY 15 1990  
Observe this plugging.

DATE 5-7-90  
INV. NO. 28075 28076  
JUN 21 1990

Signed Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow