

15-195-00361-00-02

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-00361-00-02  
Spot: NWNWSW Sec/Twnshp/Rge: 2-12S-21W  
2310 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: KOHL Well Number: 8 OWWO  
County: TREGO Total Vertical Depth: 4040 feet

Operator License No.: 31566 Conductor Pipe: Size \_\_\_\_\_ feet:  
Operator Name: BENCHMARK OIL & GAS CORPO Surface Casing: Size 8.625 feet: 174  
Address: 1515 ARAPAHOE ST STE 580 11/29 Production: Size 5.5 feet: 4024  
DENVER, CO 80202 Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

131.30

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/29/2000 9:00 AM  
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC.  
Proposal Rcvd. from: ROLAND NYP Company: BENCHMARK OIL & GAS Phone: (303) 595-9251

Proposed Plugging Method: According to KCC Rules & Regulations.  
Ordered 375 sxs cement and 600# hulls.  
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/29/2000 12:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 174'. 5 1/2" casing at 4024'. D.V. Tool at 1770' w/450 sxs cmt.  
RIH with tubing to 2340' and pumped 100 sxs cmt and 550# hulls.  
Pulled tubing to 1540' and pumped 100 sxs cement.  
Pulled tubing to 980' and circulated with 110 sxs cmt.  
Pulled all tubing and squeezed 65 sxs cmt to Max. P.S.I. 600#. S.I.P. 300#.  
Tied to 8 5/8" x 5 1/2" and pressured to 400#. Took no cement.  
Total 375 sxs 60/40 pozmix - 10% gel - 550# hulls.  
Dakota - 660' - 960'.  
Anhy. - 1750' - 1790'.  
Salt - 2070' - 2260'.

RECEIVED  
STATE CORPORATION COMMISSION  
12-4-2000  
DEC 4 2000  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY. B&L TANK SERVICE - WATER.

Plugged through: TBG

District: 04

Signed Roger L. Moses  
(TECHNICIAN)

100

INVOICED

DATE 12/5/00

INV. NO. 2001061061

Form CP-2/3

NOV 30 2000

GLICKMAN OIL CO

#BKOHL (OKMO)

2-12-21W  
NW NW SW

Costr. CO TOOLS

TREGO

County

E 2315 RB Comm

Comp. 1/23/64

IP PIP 25 BOPD + 20 BHPD  
(ARB 4024-40)

Tops	Depth	Datum
ANH	1750	+565
HEEB	3581	-1266
TOR	3605	-1290
LANS	3618	-1303
FRO ARB	3959	-1644
SOLID ARB	3974	-1659
ID	3995	-1680
NTD	4040	-1725

Casing  
8" 174:  
WAS: WOODMAN & WANNITTI & BROWN  
& FORTIER #1 KOHL, D & A  
10/3/58:  
DST 3608-48/30", 14' M, BHP 1215#:  
DST 3915-96/1', 35' SLI O & GCW,  
BHP 77-505#:  
NEW INFO: CO 3996: DD 4040:  
DST 4001-16/1', 5' M, BHP 77-44#  
FP 9-17#:  
DST 4016-31/1', 15' M, FBHP 1085#  
FP 17-26#:  
DST 4031-40/1', 450' CLN O, 180'  
MO, NY, BHP 1005-987#, FP  
17-550#:  
TD 4040: 5" 4024/50 SX  
CO TD: FU 2500' O & 150'  
W/12 HRS: SWB 3 BOPH,  
NAT'L: 4 HRS: POP:

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS