

6 040778

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NA  
NE SE NW, SEC. 14, T 10 S, R 20 W/E  
\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT  
5337

Operator License # \_\_\_\_\_

Lease Name Stithem Well # 25

Operator: Nadel and Gussman  
Name & Address 3232 First Nation Twr.  
Tulsa, Ok. 74103

County \_\_\_\_\_ Rooks 122.82  
Well Total Depth 3779 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 202' w/

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cmt. License Number \_\_\_\_\_

Address Russell, Kansas

Company to plug at: Hour: 9:00 Am Day: 21 Month: July Year: 19 87

Plugging proposal received from Frank Neff

(company name) Nadel and Gussman (phone) \_\_\_\_\_

were: 5 1/2" csg set at 3774' w/150 sks. Sq at 648' w/200 sks and 1248' w/250 sks.  
Perf at 3642' -82'. Sq w/400 sks w/packer at 3390'; cmtd. tubing and packer  
in hole, backed tubing off at 400'. Well was also Kem - packed.  
Ordered 150 sks 65/35 Poz 10% Gel 2% Lite w/1/4# Flocele and 3 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:00 AM Day: 21 Month: July Year: 19 87

ACTUAL PLUGGING REPORT Pumped in 8 5/8" and 5 1/2" csg 150 sks 65/35 Poz 10% Gel, 2% Lite mix  
and 1/4# Flocele w/3 sks Hulls.

Max Psi. 500# Shut in 250#.

RECEIVED  
STATE CORPORATION COMMISSION  
8-18-1987  
AUG 18 1987

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: CR cmt top - OK  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-18-87

INV. NO. 17867

Signed Dennis L. Hamel  
(TECHNICIAN)

Dennis L. Hamel