

4- 041422

11-12

125

15-163-02131-00-00R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - N/A

NW NE NW /4 SEC. 14 , 10 S, 20 W
4950 feet from S section line
3630 feet from E section line

Operator license# 5337

Lease Stithem 2 well # 2

Operator: Nadel & Gussman

County Rooks

Address: 3200 First National Tower
Tulsa, Oklahoma 74103

Well total depth 3786 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 160 feet
w/110 sx.

123.05

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00A.M. Day: 12 Month: November Year: 92

Plugging proposal received from: Frank Neff

Company: Nadel & Gussman Phone:

Were: 5 1/2" casing set @ 3780' w/125 sx. cement. O.H. @ 3780' -
3786'. Tubing fish @ 3048'. Squeeze 780' w/300 sx. 923' w/235 sx.
1547' w/260 sx. 1215' w/175 sx. Total cement 960 sx.
Order 300 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:15A.M. Day: 12 , Month: November , Year: 92

Actual plugging report: R.I.H. with tubing to 3018'. Spot 75 sx. cement
pull tubing to 2050'. Spot 75 sxs. cement w/100# hulls to circulate
at surface. P.O.O.H. with tubing. Hooked-up to 5 1/2" casing.
Squeeze 125 sx. cement. Max. P.S.I. 800#. S.I.P. 400#.
Hooked-up to 5 1/2" casing. Pumped in 50 sx. cement w/200# hulls.

Remarks:

Condition of casing(in hole):GOOD BAD X Anhy.plug:YES X NO
Bottom plug(in place):YES X ,CALC ,NO Dakota plug:YES X ,NO
Plugged through TUBING X , CASING . Elevation: GL

I did[X] / did not[] observe the plugging.

DATE 12-7-92

BY: 36985

Dennis L. Hamel

(agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 25 1992
11-25-1992
CONSERVATION DIVISION
WICHITA, KANSAS

HO.