

4- 041421

15-163-02159-00-00  
11-12 124 R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - N/A

NE NE SW /4 SEC. 14 , 10 S, 20 W  
2310 feet from S section line  
2970 feet from E section line

Operator license# 5337

Lease Stithem well # 22

Operator: Nadel & Gussman

County Rooks

Address: 3200 First National Tower  
Tulsa, Oklahoma 74103

Well total depth 3770 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 167 feet  
w/150 sx.

122.53

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cementing License#    

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:30A.M. Day: 12 Month: November Year: 92

Plugging proposal received from: Frank Neff

Company: Nadel & Gussman Phone:    

Were: 5 1/2" casing set @ 3769' w/150 sx. cement. Perf. @ 3579' -  
3653'. Squeeze @ 980' w/200 sx. Squeeze @ 715' w/175 sx. cement.  
560' w/180 sx. cement. 1490' w/225 sx. cement. Fish @ 3200'. Hole in  
casing @ 1700' and 1100'.  
Order 300 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 2:45P.M., Day: 12, Month: November, Year: 92

Actual plugging report: R.I.H. with tubing to 3000'. Spot 75 sx. cement  
tubing plugged. Pull tubing. Hooked-up to 5 1/2" casing pumped in 200  
sx. 60/40 pozmix - 10% gel. with 1/4# F.C. with 300# hulls.  
Max. P.S.I. 500#. S.I.P. 300#. Hooked-up to 8 5/8" S.P. Squeeze in  
75 sx. cement with 100# hulls. Max. P.S.I. 500#. S.I.P. 400#.

RECEIVED  
STATE CORPORATION COMMISSION  
11-25-1992  
NOV 25 1992

Remarks:      
Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES     NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES    , NO      
Plugged through TUBING    , CASING    . Elevation:     GL    

I did[     ] / did not[     ] observe the plugging. Dennis L. Hamel

DATE 12-2-92  
INV. NO. 36984

(agent)

INVOICED