

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02148-00-00
Spot: NWSENW Sec/Twnshp/Rge: 14-10S-20W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: STITHEM Well Number: 10
County: ROOKS Total Vertical Depth: 3784 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN, LLC
Address: 3200 FIRST PLACE TOWER
TULSA, OK 74103

Production Casing Size: 5.5 feet: 3781 125 SX CMT
Surface Casing Size: 8.625 feet: 158 125 SX CMT

1/22 98

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/19/2003 8:00 AM

Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: JOHN ROLO Company: NADEL AND GUSSMAN, LLC Phone: (785) 434-2916

Proposed 5 1/2" casing at 3781'. 8 5/8" S.P. at 158'.
Plugging Ordered 250 sxs 60/40 pozmix - 10% gel - 18 sxs gel - 500# hulls.
Method: Perf casing 975' and 1750'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/19/2003 11:30 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementers to 5 1/2" casing.
Squeezed 25 sxs cement with 300# hulls, followed with 18 sxs gel, followed with 200 sxs cement.
Max. P.S.I. 1000#. S.I.P. 400#.
8 5/8" S.P. - Squeezed 25 sxs cement with 100# hulls.
Max. P.S.I. 600#. S.I.P. 200#.

RECEIVED
8-13-2003
AUG 13 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

100

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED
DATE 8-13-03
INV. NO. 2004060397

JUL 28 2003

NADEL & GUSSMAN

#10 STITHAM

14-10-20W
NW SE NW

22

Contr. _____ ROOKS County

E 2243 Comm. _____ Comp. 10-26-51 IP 3000 BOPD (ARB)
DRAW DOWN

Tops	Depth	Datum
ANH	1670	573
HEEB	3461	-1218
LANS	3499	-1256
ARB	3780	-1537
T.D.	3784	-1541

Casing
 8" 158 ACID 1500
 5" 3781 SWB 105 BO

MARCOTTE POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

14-10-20W
NW SE NW
22