

4-042044

15-163-02132-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-

SE NE NW /4 SEC. 14, 10 S, 20 W
990 feet from S section line
2310 feet from E Section line

3/27

Operator license# 5337

Lease: Stithem Well # 3

Operator: Nadel and Gussman

County: Rooks 122, 82

Address: 3200 First National Tower
Tulsa OK 74103

Well total depth 3779 feet
Conductor Pipe: inch @ feet
Surface Pipe: 8 5/8 Inch 168 Feet
W/100 sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 27 Month: March Year 2000

Plugging proposal received from: John 'Art' Rolo

Company: Nadel & Gussman Phone: -

Were: Ordered 250 sxs 60/40 pozmix - 10% gel and 400# hulls.
5 1/2" casing set at 3775' w/150 sxs cement. O.H. at 3779'.
Perf. Anhy at 1735'. Dakota at 900'.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 6:30 P.M., Day: 27, Month: March, Year: 2000

Actual plugging report: R.I.H. with tubing to 3700'. Spotted 21 sxs gel, followed with 40 sxs cement with 300#. Pulled tubing to 1800'. Spotted 125 sxs cement to circulate at surface. POOH with tubing and squeezed casing with 30 sxs cement. Max. P.S.I. 900#. Squeezed 8 5/8" S.P. with 25 sxs cement with 100# hulls. Max. P.S.I. 300#.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING CASING Elevation: G.L.

I did[X] / did not[] observe the plugging.

INVOICED RECEIVED STATE CORPORATION COMMISSION
DATE 4/14/00 APR 12 2000
061551 4-12-2000
WICHITA, KANSAS

Dennis J. Hamel (agent)
Form CP-2/3
R