

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22217-00-00
Spot: CNENW , Sec/Twnshp/Rge: 13-12S-21W
4620 feet from S Section Line, 3560 feet from E Section Line
Lease/Unit Name: BAILEY TRUST Well Number: C 1
County: TREGO Total Vertical Depth: 4080 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

Conductor Pipe: Size feet: 132.60
Surface Casing: Size 8.625 feet: 264
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 12/12/2001 12:15 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Order 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 12/12/2001 3:15 PM

Witness Type: Plugging Operations Were Not Witnessed
KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3950' w/25 sxs. Ar buckle at 3968'.
2nd. Plug at 1750' w/25 sxs. Anhydrite 1711' - 1744'.
3rd. Plug at 950' w/100 sxs. Dakota 606' - 946'.
4th. Plug at 315' w/40 sxs. Surface pipe 264'.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Remarks: ALLIED CEMENTING COMPANY

Plugged through: DP

District: 04

Signed

RECEIVED
12-19-2001
DEC 19 2001
KCC WICHITA

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-20-01
INV. NO. 2002061081

DEC 17 2001