

4-031917

4-22

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-195-20,945-00-00

SW SW NW /4 SEC. 13, 12 S, 21 W  
2790 feet from S section line  
4950 feet from E section line

Operator license# 5364

Lease Christopher well # 1

Operator: Beren Corporation

County Trego

Address: Box 723  
Hays, Kansas 67601

Well total depth 4016 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 324 feet

130.52

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 22 Month: April Year: 94

Plugging proposal received from: Bob Grant

Company: Beren Corporation Phone: 913-628-6101

Were: Order 250 sxs. 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 1:30P.M., Day: 22, Month: April, Year: 94

Actual plugging report: 8 5/8" set @ 324' w/210 sxs. cwc. 5 1/2" set @ 4001' w/200 sxs. D.V. Tool set at 1719' w/450 sxs. O.H. 4001' - 16.5. Squeezed 5 1/2" w/250 sxs. cement blend w/500# hulls mixed in to Max. P.S.I. 1000#. Close in P.S.I. 200#. Tested 8 5/8" annulus to 300# P.S.I. w/15 sxs. cement blend. Plug complete.

Remarks: Anhy. 1702'.

Condition of casing(in hole): GOOD X BAD      Anhy.plug: YES X NO     

Bottom plug(in place): YES     , CALC X, NO      Dakota plug: YES X, NO     

Plugged through TUBING     , CASING X. Elevation: 2304 GL

I did[ X ] / did not[      ] observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

**INVOICED**  
DATE MAY 03 1994  
INV. NO. 40378

RECEIVED  
STATE CORPORATION COMMISSION  
04 29 1994  
APR 29 1994  
CONSERVATION DIVISION  
Wichita, Kansas