

GP

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
6-3-1971
JUN 3 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Alpine Drilling Co., Inc.

Complete Address 800 Bitting Bldg., Wichita, Kansas

Lease Name Weisner Well No. 1

Location S/2 NE SE Sec. 29 Twp. 12 Rge. (E) (W) 20

County Ellis Total Depth 3860'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Glenn & Smith Pipe Pulling

Address Box 156 Ellinwood, Kansas License No. 396

Operation Completed: Hour 11:30 A Day 29 Month 5 Year 1971

The above well was plugged as follows:

Total Depth 3860' 8 5/8 csg set at 253' cwc 160 sk.

5 1/2 csg set at 3855' cw 100 sk cmt.

5 1/2 csg PBTD 3680' with top perf. (3482')

Set 5 1/2 wood plug at 3450' -poured 20 gal sd -dumped 5 sk cmt W/dump bailer. (3400-3450)

Cutoff and recovered 2990' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel W/5 sk hulls, -70 sk 50-50 poz 6% -10 sk gel -

release plug and pumped 50 sk 50-50 poz 6%. Max. pres. 350 lbs. SI pres 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 6-3-71
INV. NO. 3793-W