

KANSAS
STATE CORPORATION COMMISSION

R

WELL PLUGGING SUPERVISOR'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 84-51 Location: SW SE SW
County: Ellis Sec. 29 Twp. 12 Rge. 20 (E) (W)
Name of Field or Pool: _____ Total Depth: 3917

I have this date completed supervision of plugging of:

Well No. 1 Lease Goff Groff

Operator's Full Name Sterling Drg Co

Complete Address: Sterling, Kans

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

If well is a rotary drilled dry hole did operators wait for you to arrive _____

If yes how long _____ Reason: _____

Operation Completed: Hour 9AM Day 18 Month 4 Year 58

The above well was plugged as follows:

8 5/8" at 360' circulated with cement - 5 1/2" 3916' with 75 sax cement.

P. B. to 3886', perforations 3860'.

Filled with sand to 3850', set 4 sax cement with dump bailer, pulled

3240' 5 1/2" tp 600', circulated hole with heavy mud at 600' through

5 1/2" (38 sax Gel), displaced 20 sax cement through 5 1/2" at 600', heavy

mud to 250', displaced 20 sax cement through 5 1/2" at 250', heavy mud

to 35', set rock and 10 sax cement to bottom cellar.

Mud and cement pumped with cementing pump truck.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: *Jewel M. Ogden*
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
CORPORATION COMMISSION
4-23-1958
APR 23 1958

CONSERVATION DIVISION
Wichita, Kansas

Reviewed: *J. Lewis Brock*
Field Supervisor

Signed: _____
Well Plugging Supervisor

Remarks:

PLUGGING
FIL SEC 19 T 12 R 20
BOOK PAGE 84 LINE 31