

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-32,163

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Tom-Kat, L.T.D.

Complete Address 2008 11th St., Great Bend, Ks. 67530

Lease Name Schmeidler Well No. 1

Location SW NW SW Sec. 33 Twp. 12 Rge. 20 (East) (~~West~~)

County Ellis Total Depth 3880'

Abandoned Oil Well XXX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67524 License No.

Operation Completed: Hour: 10:50 AM Day: 14 Month: 7 Year: 19 82

Plugging Operations attended by Agent?: All XXX Part None

The above well was plugged as follows:

8 5/8"-200' S.P. cuc. w/common cement. 5 1/2" set at 3880' w/100 sacks common
cement. Top perf. at 3772'. Plugged bottom w/sand & 5 sacks cement. to 3700'.
Shot pipe 4 times & recovered 2648'. Ordered 165 sacks 50/50 posmix-4% Gel.-3%
Cal.Cl., 20 sacks Gel., 5 sacks hulls & 8 5/8" plug. Pumped into S.P. w/pump truck
4 sacks hulls, 25 sacks cement, 15 sacks Gel., 70 sacks cement, 5 sacks Gel., 1
sack hulls, released plug & followed w/70 sacks cement.

Maximum pressure 500 pounds

Amount of Surface Casing: 200' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
7-19-1982
JUL 19 1982

Signed:
Conservation Division Agent

INVOICED

DATE 7-22-82
INV. NO. 683-w