

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
9-28-1970
SEP 28 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Aspen Resources LTD

Complete Address 710 One Twenty Bldg., Wichita, Kansas

Lease Name Shuts Well No. 1

Location SW NW NW Sec. 33 Twp. 12 Rge. (E) (W) 20

County Ellis Total Depth 3865

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 7 A Day 25 Month 9 Year 1970

The above well was plugged as follows:

RTD 3865' 8 5/8 csg set at 250' cwc. Cmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 9-28-70

INV. NO. 2589-W