

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Winwell 1968 Exploration Company

Complete Address: 1011 Commercial Nat. Bank Bldg., Shreveport, Louisiana 71101

Lease Name Schagel "A" Well No. 1

Location SW NW NE Sec. 36 Twp. 12 Rge. 20 (E) (W) X

County Ellis Total Depth 3495

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: _____

Plugging Contractor: Hellar Drlg.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 10A Day 12 Month 11 Year 1968

The Above well was plugged as follows:

RTD 3495' 8 5/8 csg set at 215' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cmt.

thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/14/68
INV. NO. 8814-11

Signed: Leo F. Massey
Well Plugging Supervisor