

KANSAS

STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

5-22-1980  
MAY 22 1980

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-163-21,031 (of this well)

Operator's Full Name CHAMPLIN PETROLEUM COMPANY

Complete Address 2601 NORTHWEST EXPRESSWAY, SUITE 800E OKLA. CITY, OKLA. 73112

Lease Name ROGERS Well No. "B" # 7

Location SW-SE-NE Sec. 23 Twp. 10 Rge. 20 (E) (W) W

County ROOKS Total Depth 3820 <sup>FE</sup>

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor GLENN'S CASING PULLING INC.

Address BOX 413 ELLENWOOD, KS. 67526 License No. 832

Operation Completed: Hour 2:15 PM Day 21 <sup>ST</sup> Month MAY Year 1980

The above well was plugged as follows:

8 5/8" 246 FE SP. CWC. W/ 200 FE QUICKSET. - 5 1/2" SET AT 3819 FE W/ 200 FE  
OF 50/50 POZMIX 18% SAULT. - PLUG. BACK. A BRIDGE PLUG AT 3788 FE  
PERFS 3780' to 3783 FE - BOTTOM SANDED TO 3730 FE AND 5 FE INT.  
SHOOT PIPE AT 2560 FE RECOVERED 2560 FE  
ORDERED 140 FE 50/50 POZMIX 6% GEL -> 20 FE GEL - 6 FE HULLS + 8 5/8" PLUG.  
PUT IN 3 FE HULLS -> 12 FE GEL -> 70 FE INT. + 8 FE GEL -> 3 FE HULLS  
RELEASED PLUG. AND 70 FE INT. -> MAX PRESSURE 300 LBS  
CEMENTED BY SUN CEMENTING

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Melvin Schmidt  
Well Plugging Supervisor

DATE 5-30-80  
INV. NO. 2230-W