

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- -

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Champion Petroleum Co.

Complete Address Box 9365 - Ft. Worth, Tx 76107

Lease Name Rogers 'B' Well No. #1

Location NW-NW-NE Sec. 23 Twp. 10 Rge. 20 (East) (~~West~~)

County Rooks Total Depth 3776

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing

Address Hays, Ks 67601 License No. _____

Operation Completed: Hour: 11:30 AM Day: 8 Month: 9 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" @ 210' w/160 sx common - 5 1/2" @ 3775 w/150 sx
Open hole 3775-76 - Hole in ... eq. @ 1290' -
Dakota squeezes @ 1040' w/150 sx - 70 cmt. to surface -
Ordered 275 sx 50% poz 6% gel - 20 gel - 6 hulls
Impd. in 5 5/8" 150 cmt + 2 hulls -> 20 gel -> 125 sx + 2 hulls -> PSI 250
1" in 8 5/8" 100 sx cmt + 2 hulls -> PSI shut in 150'

Amount of Surface Casing: 910'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signature _____ Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1982
9-14-1982
CONSERVATION DIVISION
Wichita, Kansas
INS. NO. 1141-W