

KANSAS

2
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
8-18-1972
AUG 18 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Champlin Petroleum Company

Complete Address -2915 N. Lincoln Oklahoma City, Oklahoma 73105

Lease Name Rogers "B" Well No. 6

Location NW NE NE Sec. 23 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3789'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by HOWCO

Address License No.

Operation Completed: Hour 2 P Day 17 Month 8 Year 1972

The above well was plugged as follows:

Total Depth 3789' 8 5/8 csg set at 212' cwc 150 sk.

5 1/2 csg set at 3789' cw 75 sk cmt.

5 1/2 csg Lane Wells Plug set at 3707'.

5 1/2 csg perf. (3776-3778) No pipe recovered.

Ran 114 jts tbg set at 3420' -pumped 100 lbs hulls -circulated 30 sk gel & water -

displaced 25 sk cmt. -Pulled 94 jts tbg set at 600' -circulated 50 sk cmt to surface.

Pulled remaining 20 jts tbg & capped 5 1/2 csg W/15 sk cmt.

Pumped 50 sk cmt down annulus with 300 lbs pres.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Mussen
Well Plugging Supervisor

INVOICED

DATE 8-21-72

INV. NO. 6191-W