

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-195-30098-00-00

JAN 3 1966  
01-03-1966  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Clinton Oil Company,  
Complete Address: 6810 W. Hwy. US 54, Wichita, Kansas.  
Lease Name Blakely Well No. 1-X  
Location CS/1/2-NW-NE Sec. 29 Twp. 12 Rge. (E) (W) 21  
County Irego Total Depth 3955  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Knight Casing Pulling Company,  
Address: Box #405, Chase, Kansas. License No. 436  
Operation Completed: Hour 2:00PM Day 30 Month 12 Year 1965

The Above well was plugged as follows:

248'--8 5/8" Surface pipe, cement circulated.  
3954'--5 1/2" Production casing cemented with 125 Sx. Top of cement @3452'  
(Temp. Survey). Well Plugged back to 3935, Top perforations @ 3582.  
Pushed plug to 3550', sanded to 3540' and set 5 Sx. cement with dump  
bailer. Pulled 5 1/2", bailed hole to 400', set wood and rock bridge and  
filled hole to bottom of cellar with 6 yards Redi-Mix.  
(Recovered 3244' 5 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 1/3/66  
INV. NO. 2523-W