

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

15195-01433-00-00

FILE NO. 12-39

LOCATION SW SE SW

SEC. 33 TWP. 12 RGE. 21

Dry Hole X Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Merrill

Operator Petroleum Inc Address RFD # 2 Great Bend, Kans

Field \_\_\_\_\_ County Trego

Total Depth 3889 Feet.

Plugging Contractor Morgan Pipe Pulling

Plugging Contractor's License No. 43

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 200' circulated w/ cement - 5 1/2" at 3884' with

40 sax cement and 40 Cubic feet stratocrete behind.

Filled with chat to 3870', set 4 sax cement with dump bailer,

pulled 2400' 5 1/2" - circulated hole with heavy mud through 5 1/2" -

pumped cementing plug to 600', followed by 100 sax cement and 100

Cubic feet stratocrete, filling hole to 0'.

*Edson Peck*  
District Conservation Agent

Date 7-10-57

**RECEIVED**  
STATE CORPORATION COMMISSION  
07-13-1957  
**JUL 13 1957**  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 33 T. 12 R. 21  
BOOK PAGE 12 LINE 39