

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-163-23,161 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Calvin Noah OPERATOR'S LICENSE NO. 5616

ADDRESS 329 N. Birch, Valley Center, KS 67147 PHONE # (316) 755-0051

LEASE (FARM) Allphin WELL NO. #1 WELL LOCATION Approx. 50' W of NE SE NW COUNTY Rooks

SEC. 33 TWP. 10S RGE. 20 (E) or (W) TOTAL DEPTH 3225' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 260' CEMENTED WITH 60-40 posmix SACKS 170

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 1625' w/25 sx; 2nd plug @ 850' w/100 sx; 3rd plug @ 300' w/40 sx; 4th plug @ 40' w/10 sx; rathole 15 sx; Total 190 sx 60-40 posmix 6% gel 3% cc.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? No
(If not explain.) Sent to Operator to complete

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 12:30 p.m. 5-6-91

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley

PHONE # (913) 674-5768 STATE CORPORATION COMMISSION

ADDRESS 216 E. McFarland, Hill City, KS 67642

RECEIVED
6-3-1991
JUN 03 1991

PLUGGING CONTRACTOR Abercrombie RTD, Inc. LICENSE NO. 30684 CONSERVATION DIVISION
Wichita, Kansas

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wharton
(Operator or Agent)

DATE: May 31, 1991