

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31134
Name: Armor Petroleum, Inc.
Address 1: P.O. Box 4625
Address 2: _____
City: Wichita Falls State: TX Zip: 76308 + 0625
Contact Person: Jerry Arthur
Phone: (940) 692-5001 ext 17

API No. 15 - 119-10260-0500
If pre 1967, supply original completion date: 9/10/1960
Spot Description: _____
____ NE Sec. 23 Twp. 34 S. R. 27 East West
1,220 Feet from North / South Line of Section
1,320 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Meade
Lease Name: Merkle Well #: # 1

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8" Set at: 1400' Cemented with: 900 Sacks
Production Casing Size: 5 1/2" Set at: 6219' Cemented with: 200 Sacks

List (ALL) Perforations and Bridge Plug Sets:
6114' - 6132' (Morrow) & 6020' - 6026' , 6035' - 6039' (Chester)

Elevation: 2427' (G.L. / K.B.) T.D.: 6274' PBTD: 6136' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

CIBP @ 5970' w/ 2 sks cement . Pull casing (+/- 2000') . 100 sk Cement Plug 1450' - 1030' . 40 sks cement plug 550'- 400' and 15 sks cement 54' - 4' .

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No
If ACO-1 not filed, explain why:

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 07 2009

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Jerry Arthur
Address: P.O. Box 4625 City: Wichita Falls, TX Zip: 76308 + _____
Phone: (____) 940-692-5001
Plugging Contractor License #: 33338 Name: Orr Enterprises, Inc
Address 1: P.O. Box 1706 Address 2: _____
City: Duncan State: OK Zip: 73534 + 1706
Phone: (580) 467-0258
Proposed Date of Plugging (if known): ASAP

CONSERVATION DIVISION
WICHITA, KS

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 12/4/09 Authorized Operator / Agent: Jerry Arthur, Engineer
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

D6



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

ARMOR PETROLEUM, INC.
PO BOX 4625
WICHITA FALLS, TX 76308-0625

December 08, 2009

Re: MERKLE UNIT #1
API 15-119-10260-00-00
23-34S-27W, 1220 FNL 1320 FEL
MEADE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after June 6, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888