



KANSAS CORPORATION COMMISSION 1033735  
OIL & GAS CONSERVATION DIVISION

Form CP-1  
March 2009  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

OPERATOR: License #: 5056  
Name: Holl, F.G., Company L.L.C.  
Address 1: 9431 E CENTRAL STE 100  
Address 2: \_\_\_\_\_  
City: WICHITA State: KS Zip: 67206 + 2563  
Contact Person: Loveness Mpanje  
Phone: (316) 684-8481

API No. 15-047-20563-00-00  
If pre 1967, supply original completion date: \_\_\_\_\_  
Spot Description: \_\_\_\_\_  
SE SE SE Sec. 3 Twp. 25 S. R. 17  East  West  
330 Feet from  North /  South Line of Section  
330 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Edwards  
Lease Name: MCKINNEY C Well #: 1-3

Check One:  Oil Well  Gas Well  OG  D&A  Cathodic  Water Supply Well  Other: \_\_\_\_\_  
 SWD Permit #: \_\_\_\_\_  ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8.6250 Set at: 254 Cemented with: 225 Sacks  
Production Casing Size: 4.50 Set at: 4584 Cemented with: 250 Sacks

List (ALL) Perforations and Bridge Plug Sets:

Attached

Elevation: 2130 ( G.L. /  K.B.) T.D.: 4585 PBTD: \_\_\_\_\_ Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Junk in Hole  Casing Leak at: \_\_\_\_\_  
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Heavy mud, hull, cement and plug according to KCC specifications

Is Well Log attached to this application?  Yes  No Is ACO-1 filed?  Yes  No

If ACO-1 not filed, explain why:

RECEIVED  
DEC 11 2009  
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Rob Long

Address: 701 E. Santa Fe City: Ellinwood State: KS Zip: 67526 + \_\_\_\_\_

Phone: (620) 793-0915

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc.

Address 1: 190 US HWY 56 Address 2: \_\_\_\_\_

City: ELLINWOOD State: KS Zip: 67526 + \_\_\_\_\_

Phone: (620) 727-3410

Proposed Date of Plugging (if known): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Submitted Electronically

Dist 1  
PPT

Form	CP1 - Well Plugging Application
Operator	Holl, F.G., Company L.L.C.
Well Name	MCKINNEY C 1-3
Doc ID	1033735

Perforations And Bridge Plug Sets

4425	4429	Mississippi	

RECEIVED  
DEC 11 2009  
KCC WICHITA

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- McKINNEY "C" 1-3  
Located: SE SE SE, Section 3-25S-17W, Edwards County,  
Kansas

OWNER: F. G. Moll  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 13, 1979  
COMPLETED: September 20, 1979

TOTAL DEPTH: 4585

LOG

- 0 - 30 Surface Soil and Clay
- 30 - 160 Sand
- 160 - 254 Shale
- 254 - 532 Red Beds and Shale
- 532 - 1165 Shale and Sand
- 1165 - 1177 Anhydrite
- 1177 - 1580 Shale
- 1580 - 2234 Shale and Shells
- 2234 - 4450 Lime and Shale
- 4450 - 4585 Chert and Lime

CASING RECORD

Ran 6 joints used 24#, 8 5/8" casing, 239.27' set at 254' K.B. with 225 sacks 60/40 Pozmix with 3% cc. Plug down at 1:15 AM, 9-13-79, by Howco.

RECEIVED  
DEC 11 2009  
KCC WICHITA

Ran 128 joints new 10.5# casing, 4 1/2", 4574.80' set at 4584' K.B. Cemented with 150 sacks Howco Light, followed with 100 sacks Pozmix #1 with 18% salt, 5# gilsonite, 1/8# floccul and 3/4 of 1% CFR-2 per sack. 250 gal. mud flush and 20 bbl. salt flush ahead of cement. Plug down at 1:00 AM, 9-20-79.

*JMP*

Deviation Surveys: 3/4° at 2234'  
3/4° at 4450'



Mark Parkinson, Governor  
Thomas E. Wright, Chairman  
Michael C. Moffet, Commissioner  
Joseph F. Harkins, Commissioner

December 11, 2009

Loveness Mpanje  
Holl, F.G., Company L.L.C.  
9431 E CENTRAL STE 100  
WICHITA, KS 67206-2563

Re: Plugging Application  
API 15-047-20563-00-00  
MCKINNEY C 1-3  
SE/4 Sec.03-25S-17W  
Edwards County, Kansas

Dear Loveness Mpanje:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after June 09, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,  
Production Department Supervisor

cc: District 1

(620) 225-8888