



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 3 1972  
CONSERVATION DIVISION  
Wichita, Kansas

01-03-1972

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-195-30129-00-00

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Braden-Deem, Incorporated,

Complete Address: 200 East First, Wichita, Kansas.

Lease Name: Merrill Well No. 1

Location: CS/2-NE-NW Sec. 34 Twp. 12 Rge. (E)(W) 21

County: Trego Total Depth 3909' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

112'--10 3/4" Surface casing, cement circulated with 120 Sx.  
1660'--7" DD Intermediate String casing cement circulated with 400 Sx.  
3898'--5 1/2" Production casing cemented on bottom with 75 Sx. Well plugged back to 3880'. Top of perforations @ 3852'.

Sand well back to 3840' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing, set rock bridge @ 900' and fill from 900' to 550' with 3 yards Redi-Mix. Fill hole from 550' to 250', set rock bridge and fill from 250' to bottom of cellar with 2 yards Redi-Mix.

Very truly yours,

W. L. Decker  
Conservation Division Agent