



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 27 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 08-27-1968

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

15-195-20084-00-00

Dear Sir:

Mr. Herb Mason of Dunne-Gardner Drlg. Co. Inc., has this date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company,

Complete Address: 410 4th National Bank Bldg., Wichita, Kansas.

Lease Name: Merrill Well No. 1

Location: E/2-SW-NW Sec. 34 Twp. 12 Rge. (E)(W) 21

County: Trego Total Depth 3936 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mason was instructed to plug the well as follows:

140'--8 5/8" Surface casing, cement circulated with 125 Sx.
Top of Dakota section @ 585'.

Circulate hole with heavy mud. Pull DP to 810' and displace 100 Sx.
cement thru DP. Pull DP to 155' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

J. B. Nichols
 Conservation Division Agent