



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-195-20217-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 11 1973  
07-11-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Kelso Casing Pulling has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply, Incorporated,

Complete Address: Box #169, Russell, Kansas.

Lease Name: Merrill Well No. 1

Location: NW-NW-NE Sec. 34 Twp. 12 Rge. (E)(W) 21

County: Trego Total Depth 3880' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Kelso was instructed to plug the well as follows:

215'-- 8 5/8" Surface casing, cement circulated with 150 Sx.

3876'-- 4 1/2" Production casing cemented on bottom with 150 Sx.

Push plug to 3600', sand back to 3590' and set 4 Sx. cement with Dump bailer.  
Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150  
Cu. Ft. cement, staged.

Very truly yours,

*H. L. Nichols*  
Conservation Division Agent