



GEORGE DOCKING Governor  
 MARION BEATTY Chairman  
 HARRY G. WILES Commissioner  
 RICHARD C. BYRD Commissioner  
 RAYMOND B. HARVEY Secretary  
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS  
 JEWEL M. OGDEN, Director

RECEIVED  
STATE CORPORATION COMMISSION

NOV 25 1959  
11-25-1959  
CONSERVATION DIVISION  
Wichita, Kansas

Jewel M. Ogden, Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

15-195-01037-00-00

Dear Sir:

I have this date Nov 17, 1959, authorized the following plugging operation:

Operator's Full Name: Davis Bras.  
 Complete Address: 5 1/2 East Third St - Tulsa Okla.  
 Lease Name: Merrill Well No. 1  
 Location: N 7 E 7 E Sec. 34 Twp. 12 Rge. 21 (E) (W)  
 County: Mingo Total Depth: 3923  
 Oil Well  Gas Well  Input Well  SWD Well  D & A   
 Other well as hereafter indicated: \_\_\_\_\_

Operator was instructed to plug well as follows:

Run Pitts circulate hole with heavy mud  
set cementing plug at 600' and displace 170 sack  
cement thru drill pipe heavy mud to 240' set  
cementing plug and displace 15 sack cement  
heavy mud to 40' set and tie cementing plug  
in place dump 1/2 sack hulls and 10 sack  
cement, cementing to base of cellar.

Very truly yours,

Signed: Robert P. Leiker  
 Conservation Division Agent