

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 3 1966

CONSERVATION DIV.
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Liben Dry Co. has this
date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Okmas Oil Co.

Complete Address: 1130 Wichita Plaza - Wichita Kan.

Lease Name: Roseman Well No. 1

Location: Sw-Se-Ne Sec 34 Twp. 10 Rge. 20 (E)(W)

County Rooks Total Depth 3730 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Norwood was instructed to plug the well as follows:

Jet pits circulate hole with heavy mud, set cementing plug at 540 ft.,
and displaced 20 sac cement thru drill pipe, heavy mud to 180 ft.,
set plug and 20 sac cement, heavy mud to 40 ft., set plug 1/2 sac hulls
and 10 sac cement.

Very truly yours,

Gilbert R. Liker
Conservation Division Agent