

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 04 1976

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Christopher of R&W Drlg. has this

date requested permission to plug the following described well:

Mr. Christopher guarantees payment of the plugging fee.

Operator's full Name: Thornton E. Anderson

Complete Address: Suite 746, 300 W. Douglas, Wichita, Ks.

Lease Name: Harlan Well No. 1

Location: W/2 NW NE SW Sec. 34 Twp. 10 Rge. (E)(W) 20

County: Rooks Total Depth 3731' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Christopher was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 600' thru drill

pipe. Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey  
Conservation Division Agent