

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Company,

Complete Address: Box # 287, Great Bend, Kansas.

Lease Name: Tribble Well No. 1

Location: NE-NE-NE Sec. 3 Twp. 10 Rge. (E)(W) 21

County Graham Total Depth 3861 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

1479'--8 5/8" Surface pipe, cement circulated with 1050 Sx. cement.
3848'--5 1/2" Production casing cemented with 200 Sx. Well plugged back to 3445'. Top perforations @ 3309'.

Push plug to 3290', sand back to 3275' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing, set 10' rock bridge @ 1479' and set 10 Sx. cement on top. Set 10' rock bridge @ 500' and set 10 Sx. cement on top. Fill hole with mud to 40', set 10' rock bridge and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent