

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By, Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1974
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co., Inc has this date requested permission to plug the following described well:Mr. Wasinger guarantees payment of the plugging fee.Operator's full Name: Phillips Petroleum Company,Complete Address: P. O. Box #287, Great Bend, Kansas.Lease Name: Tribble Well No. 4Location: 330' FWL & 330' FNL-NE/4 Sec. 3 Twp. 10 Rge. (E)(W) 21County: Graham Total Depth 3881' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Wasinger was instructed to plug the well as follows:291'--8 5/8" Surface casing, cement circulated with 300 Sx.
3872'--5 1/2" Production casing cemented on bottom with 200 Sx. (Open hole
Completion). Found 5 1/2" casing had been squeezed into surface w/ cement.Sanded well back to 3860' and set 5 Sx. cement with dump bailer. Pull
5 1/2" casing and squeeze well with 1 sacks hulls, 25 sacks gel and 190 Cu.
Ft. cement, staged.

Very truly yours,

Conservation Division Agent