

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

MAY 23 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Carmen Soukup of Phillips Petroleum Co. has this date requested permission to plug the following described well:

Mr. Soukup guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Company,

Complete Address: Box #287, Great Bend, Kansas.

Lease Name: Tribble Well No. 3

Location: SW RTCC
NE-NE-NE Sec. 3 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3632 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Soukup was instructed to plug the well as follows:

1634' -- 8 5/8" Surface pipe, cement circulated.
3821' -- 5 1/2" Production casing cemented with 200 Sx. Well
plugged back to 3632'. Top perforations from 3502' to 3508'.

Sand well back to 3480' and set 5 Sx. cement with dump bailer.

Set rock bridge @ 500' and 25 Sx. cement. Fill hole with mud
from top of cement to 30', and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols

Conservation Division Agent