

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 4 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co., Inc has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Company,

Complete Address: Box #287, Great Bend, Kansas.

Lease Name: Morel Well No. 3

Location: SW-SW-SE Sec. 3 Twp. 10 Rge. (E)(W)21

County: Graham Total Depth 3858' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

1817'---8 5/8" Surface casing, cement circulated with 955 Sx.
3850'---5 1/2" Production casing cemented on bottom with 200 Sx. Well plugged back to 3795'. Top of perforations @ 3517.

Push plug to 3400', sand to 3350' and set 5 Sx. cement with dump bailer.

Pull 5 1/2" casing and squeeze well with 35 sacks gel and 60 Sx. cement.

Very truly yours,

Conservation Division Agent