

15-065-01682-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 12 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co., Inc. has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Company,

Complete Address: Box #287, Great Bend, Kansas.

Lease Name: Morel Well No. 2

Location: NW-SW-SE Sec. 3 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3869' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

1830'--8 5/8" Surface casing, cement circulated with 1050 Sx. cement.
3860'--5 1/2" Production casing cemented on bottom with 200 Sx. (Open Hole Completion).

Sand well back to 3850' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing, check fluid level, if below 1000' set wood & rock bridge and fill hole with Redi-Mix cement.

Very truly yours,

H. L. Fike
Conservation Division Agent