



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Perkins of Rocket-Schusterman has this
date requested permission to plug the following described well:

Mr. Perkins guarantees payment of the plugging fee.

Operator's full Name: Rocket-Schusterman Oil Account,

Complete Address: 1209 Mid-Continent Building, Tulsa, Oklahoma.

Lease Name: Miller Well No. 9

Location: SE-SW-SW Sec. 3 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3905' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Perkins was instructed to plug the well as follows:

198'--8 5/8" Surface casing, cement circulated.
3904'--5 1/2" Production casing cemented on bottom. Top perforations from
3804' to 3811'. Well plugged back to 3832'. 5 1/2" has been squeezed in
the Cedar Hills.

Squeeze well with 3 sacks hulls, 30 sacks gel and 85 Sx. cement, staged.
Attempt to pump down annulus.

Very truly yours,

A. L. Nichols
Conservation Division Agent