

Amended

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33936
Name: Charles N. Griffin
Address 1: P.O. Box 670
Address 2: _____
City: Byers State: CO Zip: 80103 + _____
Contact Person: Charles Griffin
Phone: (620) 680-1262

API No. 15 - 185-23498-0000
If pre 1967, supply original completion date: _____
Spot Description: _____
- - - E/2 SW Sec. 27 Twp. 22 S. R. 11 East West
1,330 Feet from North / South Line of Section
2,130 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Stafford
Lease Name: Curtis Well #: 2

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8" Set at: 250' Cemented with: N/A Sacks
Production Casing Size: 5 1/2" Set at: 3646' Cemented with: 150 Sacks

List (ALL) Perforations and Bridge Plug Sets:

3424' - 3426' 3383' - 3388' 3318' - 3323' 3290' - 3292' *sand @ 3220 + 5sks.*

Elevation: 1797' (G.L. / K.B.) T.D.: 3648' PBTD: 3410' Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

as per KCC

600 109d 50sks. 280 50sks. 40' 20sks

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

*pipe recovery.
2650*

RECEIVED
DEC 11 2009
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Charles Griffin

Address: P.O. Box 670 City: Byers State: CO Zip: 80103 + _____

Phone: (620) 680-1262

Plugging Contractor License #: 31925 Name: Quality Well Service

Address 1: 190th US 56 Highway Address 2: _____

City: Ellinwood State: KS Zip: 67526 + _____

Phone: (620) 727-3410

Proposed Date of Plugging (if known): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10-01-09 Authorized Operator / Agent: _____

(Signature)

*Dist 1
AKS*

Quality Well Service, Inc.

190 US Highway 56
Ellinwood, KS 67526

Invoice

Date	Invoice #
10/13/2009	1120

Bill To
Charles N. Griffin P.O. Box 670 Byers, CO 80103

P.O. No.	Terms	Lease Name
	Net	Curtis #2

Description	Qty	Rate	Amount
Rig Time	14.5	185.00	2,682.50T
Sand	1	35.00	35.00T
Shots	2	300.00	600.00T
Water Truck	5	75.00	375.00T
Backhoe	2	75.00	150.00T
Phone Calls	1	15.00	15.00T
Clerical	1	20.00	20.00T
Wiping Rubber	1	20.00	20.00T
<p>10/01/09:</p> <p>Drove to location; Sanded off bottom. Loaded hole with water. Drove home.</p> <p>10/02/09:</p> <p>Drove to location and Raised pole. Dug Cellar; Unpacked casing head. Set floor. Checked hole; Sand was at 3,220'. Bailed 5 sacks cement with bailer. Pulled slips. Shut down, too windy. Drove home.</p> <p>10/05/09:</p> <p>Drove to location; Ripped casing @ 2,810' and 2,650'. Pipe came free at 2,650'. Pulled casing up to 600'; Pumped 10 gel and 50 sacks. Pulled to 280'; Pumped 50 sacks. Pulled to 40'; Pumped 20 sacks. Tore down floor & rig. Cleaned up location.</p>			

RECEIVED
DEC 11 2009
KCC WICHITA

Subtotal	\$3,897.50
Sales Tax (6.3%)	\$245.54
Total	\$4,143.04