

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

15-051-20843-00-00
 WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-051-20.843

LEASE NAME Karlin

WELL NUMBER #3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 31 TWP. 12 RGE. 17 (X) or (W)

COUNTY Ellis

Date Well Completed 8/24/72

Plugging Commenced 1/21/92

Plugging Completed 1/21/92

LEASE OPERATOR Oil Producers Inc. of Kansas

ADDRESS PO Box 8647 2400 N. Woodlawn Wichita, KS 67208

PHONE# (316) 681-0231 OPERATORS LICENSE NO. 8061

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/18/92 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached?

Producing Formation Arbuckle/Toronto Depth to Top 3624 Bottom 3627 T.D. 3627

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	3624-3627	0	298	8 5/8	298	0
LKC	3352-54	0	3624	4 1/2	4624	0
LKC	3328-3332					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Perf. Anhydrite 1300', Perf. Dakotse 720', ran 2 3/8" tbg to 3000', Spotted 100 sx 65-35 Poz w 1250" hulls, pulled tbg to 1600', pumped 60 sx 65-35 Poz to surface, pulled out of hole w/tbg; pumped 16sx 65-35 Poz, pressure 600 PSI, tied onto 85/8" Annulur pumped 150 sx 65-35 Poz Total sx 325 -

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor BJ Titan/Baker Well License No.

Address Hays

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oil Producers Inc. Of Kansas

STATE OF KS COUNTY OF Sedg., ss.

John S. Weir (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well, as filed with the same are true and correct, so help me God.

(Signature) John S. Weir

(Address) PO Box 8647 Wichita

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 19 92

Sheryl L. Murphy
 Notary Public

My Commission Expires: 12-19-92