

15-051-04357-0000
WELL PLUGGING RECORD

Ellis County. Sec. 31 Twp. 12 S Rge. (E) 17 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE/4 NE/4 SW/4

Lease Owner Messman-Rinehart Oil Company

Lease Name Staab Well No. 1

Office Address 1432 Wichita Plaza Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 21 19 63

Application for plugging filed June 21 1963

Application for plugging approved June 21 1963

Plugging commenced June 22 1963

Plugging completed June 22 19 63

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Eldon Petty, Box 326, Hays, Kansas

Name of Conservation Agent who supervised plugging of this well

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3674 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 500 ft. w/20 sx. cement.
Push plug 240 ft. w/ $\frac{1}{4}$ sk. hulls and
20 sx. cement. Set Plug at 40 ft. w/ $\frac{1}{2}$ sk.
hulls and 10 sx. cement. By Globe Cement Co.

RECEIVED
STATE CORPORATION COMMISSION
7-2-1963
JUL 2 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Messman-Rinehart Oil Company
Address 1432 Wichita Plaza Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) or (owner of)

J. A. Gilliland (employee of owner) ~~or (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me Gd.

(Signature)

1432 Wichita Plaza Bldg., Wichita 2, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of June, 1963

My commission expires December 1, 1964

~~Barbara J. Scott,~~ *Notary Public.*

15-051-04357-00-00

NO. 1 SHALE

Well Record:

Location:	SE/4 NE/4 SW/4 Section 31-125-17W Ellis County, Kansas	Commenced:	June 11, 1963
		Completed:	June 21, 1963
Operator:	Hessman-Rinehart Oil Company 1632 Wichita Plaza Bldg. Wichita 2, Kansas	Elevation:	2088' K/B
		Production:	9 & A
Contractor:	Hessman-Rinehart Oil Company 1632 Wichita Plaza Bldg. Wichita 2, Kansas		

Casing Record: 8-5/8" cas. @ 247' w/185 cu. cement

* * * * *

Clay	40
Sand	55
Shale & Shells	175
Shells & Shale	247
Shale & Shells	598
Sand	650
Shale & Shells	770
Sand	930
Shale & Red Bed	1315
Anhydrite	1360
Shale & Lime	1435
Shale	2080
Shale & Shells	2270
Lime	2415
Lime & Shale	2620
Shale & Lime	2735
Lime & Shale	2995
Shale & Lime	3180
Lime	3610
Conglomerate	3635
Conglomerate (cherty)	3674 A.T.D.

Sample Tags:

3310' - Meebner (-1272)
3379' - Lansing (-1291)
3596' - Base Kansas City (-1508)
3603' - Shaley Conglomerate (-1515)
3635' - Cherty Conglomerate (-1547)

The undersigned, HESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

HESSMAN-RINEHART OIL COMPANY

By:

J. A. Gilliland

J. A. Gilliland

Subscribed and sworn to before me
this 20th day of June, 1963

Barbara J. Scott
Barbara J. Scott, Notary Public

My Commission Expires: December 1, 1964

RECEIVED
STATE CORPORATION COMMISSION
JUL 2 - 1963
JUL 2 1963
CONSERVATION DIVISION
Wichita, Kansas