

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-051-00960-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Ellis County, Sec. 31 Twp. 12S Rge. 17W (E) (W)

Location as "NE/CNWxSWx" or footage from lines NE NW NE

Lease Owner Thunderbird Drilling, Inc.

Lease Name Karlin Well No. 1

Office Address 1311 Union National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 5, 1955

Application for plugging filed November 5 19 55

Application for plugging approved November 5 19 55

Plugging commenced November 5 19 55

Plugging completed November 5 19 55

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 36.35 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		8 5/8" set @ 202'		with 125 sacks of cement, 2% Gel, 2 sacks Calcium Chloride		
		No Oil String				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged Hole. Bottom plug at 195', cemented with 1/3 sack Hulls and 15 sacks of cement. Top plug at 35' with 1/3 sack Hulls and 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Thunderbird Drilling, Inc.

Address 1311 Union National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Charles W. Aikins, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Aikins, Jr.

1311 Union National Bank Bldg.

SUBSCRIBED AND SWORN TO before me this 8th day of November, 1955, Wichita, Kansas

Leta Helm Notary Public.

My commission expires August 25, 1956



11-9-1955

PLUGGING
FILE SEC 31 T 12 R 17W
BOOK PAGE 19 LINE 26

15-051-00960-00-00

KARLIN #1

LOCATION: NE NW NE - Sec. 31,
Twp. 12.S, Rge. 11.W
Ellis County, Kansas

CONTRACTOR: Thunderbird Drilling, Inc.
1311 Union National Bank Building
Wichita, Kansas

SURFACE CASING: 202' of 8 5/8" cemented with 125
sacks of cement, 2% Gel, 2 sacks
Calcium Chloride

OIL STRING: None

ELEVATION: 2073' K. B.
2070' D. F.
2068' G. L.

COMMENCED: October 24, 1955

COMPLETED: November 5, 1955

WELL LOG


0 -	60	Soil & Rock
60 -	202	Shale & Shells
202 -	480	Shale
480 -	960	Sand & Shale
960 -	1303	Red Bed
1303 -	1345	Anhydrite
1345 -	2015	Shale & Shells
2015 -	2240	Lime
2240 -	2945	Lime & Shale
2945 -	3303	Lime
3303 -	3345	Lime & Shale
3345 -	3560	Lime
3560 -	3630	Lime & Shale
3630 -	3635	Lime
3635		Rotary Total Depth

The undersigned, Charles W. Aikins, Jr., an officer of Thunderbird Drilling, Inc., hereby certifies that the above is a true and correct log of the formations encountered in the drilling of the #1 Karlin as shown in the daily drilling reports.


THUNDERBIRD DRILLING, INC.


Charles W. Aikins, Jr., Pres.

Subscribed and sworn to before me
this 8th day of November, 1955.


Leta Helm - Notary Public

My commission expires:
August 25, 1956



11-9-1955