

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 31164  
Name: Double B Oil Company  
Address 1: 389 Grove Terr  
Address 2: \_\_\_\_\_  
City: Great Bend State: KS Zip: 67530 + \_\_\_\_\_  
Contact Person: Clarence Barta  
Phone: (620) 792-6237  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 08/25/1960 009-02051-0000  
Spot Description: \_\_\_\_\_  
SW SW SW Sec. 23 Twp. 20 S. R. 14  East  West  
330 Feet from  North /  South Line of Section  
330 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Barton  
Lease Name: Janne Well #: 1  
Date Well Completed: 8/25/1960  
The plugging proposal was approved on: 08/17/2009 (Date)  
by: Pat Staube (KCC District Agent's Name)  
Plugging Commenced: 08/19/2009  
Plugging Completed: 08/19/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8"	268'	0'
		Production	5-1/2"	3549-1/2'	0'

RECEIVED  
AUG 25 2009  
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Sanded bottom up to 3020'. Perforated 5-1/2" casing @ 1450'-815'-450'. Ran 2-3/8" tubing to 2987'. Pumped 5 bbls fresh water. Spotted 16 sks gel & 10 sks 60/40 poz mix w/4% gel. Pulled tubing up to 1447'. Mixed 180 sks 60/40 poz mix w/4% gel w/300# hulls & circulated cement to surface in 5-1/2" casing. Pulled tubing. Hooked to 5-1/2" casing. Mixed 10 sks 60/40 poz mix w/4% gel & pressured up to 500#. Shut in 200#. Hooked to Annulus. Mixed 50 sks 60/40 poz mix w/4% gel & pressured to 150#. Shut in 75#.

Plugging Contractor License #: 6901 Name: D.S. & W. Well Servicing, Inc.  
Address 1: 1822 24th Street Address 2: \_\_\_\_\_  
City: Great Bend State: Kansas Zip: 67530 + \_\_\_\_\_  
Phone: (620) 793-5838  
Name of Party Responsible for Plugging Fees: Double B Oil Company  
State of Kansas County, Barton, ss.  
Edward S. Nemnich  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Edward S. Nemnich

PK