



Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION 1032162
 OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
 K.A.R. 82-3-117

Form CP-4
 March 2009
 Type or Print on this Form
 Form must be Signed
 All blanks must be Filled

OPERATOR: License #: 3842
 Name: Larson Engineering, Inc. dba Larson Operating Company
 Address 1: 562 W STATE RD 4
 Address 2: _____
 City: OLMITZ State: KS Zip: 67564 + 8561
 Contact Person: Tom Larson
 Phone: (620) 653-7368
 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Viola Depth to Top: 3251 Bottom: 3255 T.D. 3286
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15-197-20167-00-00
 Spot Description: _____
 NW SE SE NW Sec. 32 Twp. 14 S. R. 10 East West
3,020 Feet from North / South Line of Section
3,040 Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: Wabaunsee
 Lease Name: ELDRIDGE Well #: 32-1
 Date Well Completed: 11/09/1984
 The plugging proposal was approved on: 10/5/2009 (Date)
 by: Mike Heffern (KCC District Agent's Name)
 Plugging Commenced: 10/06/2009
 Plugging Completed: 10/07/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Viola	oil & water	surface	8.625	310	0
		production	5.5	3415	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated 4 holes @ 1500' & 4 holes @ 350'. TIH w/ 2-7/8" tubing to 3175'. RU Consolidated Oilwell Svc. Spotted 35 sx w/ 1% CC & hulls @ 3175'. Displaced w/ 500# gel spacer. Pulled tubing to 1495'. Spotted 25 sx @ 1495'. Displaced w/ 500# gel spacer. Pulled tubing to 351'. Spotted 100 sx @ 351' & circulate cement to surface. Pulled tubing and topped off casing. Plugged w/ 160 sx 60/40 poz w/ 4% gel. Plugging complete 10/7/2009.

Plugging Contractor License #: 33961 Name: Consolidated Oil Well Services LLC
 Address 1: 1322 S GRANT Address 2: PO BOX 884
 City: CHANUTE State: KS Zip: 66720 + _____
 Phone: (620) 431-9210
 Name of Party Responsible for Plugging Fees: Larson Engineering, Inc.
 State of Barton County, Kansas, ss. _____
Thomas Larson, President Employee of Operator or Operator on above-described well,
 (Print Name)

RECEIVED
 OCT 27 2009
 KCC WICHITA

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Submitted Electronically

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten Signature]