

15-163-03530-0000

f

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

SEP 25 1978
09-25-78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Sohio Petroleum Co.

Complete Address Box 673, Russell, Kansas 67665

Lease Name Sutor "A" Well No. 2

Location SE NE SE Sec. 13 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3925'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 1:10 P Day 20 Month 9 Year 1978

The above well was plugged as follows:

Total Depth 3925' 8 5/8 csg set 1620' cwc 800 sk.

5 1/2 csg set 3923' cw 200 sk cem.

5 1/2 csg PBTB 3722' with top perf. 3463'

Set 1 1/2" wood plugs at 3418' - 3 poured sd to 3200' - dumped 5 sk cem W/dump bailer.

Cutoff & recovered 2583' of 5 1/2 csg. (3200-3170)

Pumped 20 sk gel & water -released 8 5/8 plug & pumped 50 sk 50-50 poz 2% -diaplaced

with 8 sk gel & water & capped with 25 sk 50-50 poz 2% & shutin.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 9-26-78

INV. NO. 8164-W