

15-163-03153-0000

Form CP-3  
Rev. 6-4-68

f

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

OCT - 2 1978  
10-02-78  
CONSERVATION DIVISION  
Wichita, Kansas

API Number 15 - -

Operator's Full Name Sohio Petroleum Co.

Complete Address Box 673, Russell, Kansas 67665

Lease Name Sutor "A" Well No. 3

Location 1NW SE SE Sec. 13 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3761'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 12:40 P Day 30 Month 9 Year 1978

The above well was plugged as follows:

Total Depth 3761' 8 5/8 csg set 1616' cwc 800 sk.

5 1/2 csg set 3761' cw 150 sk cem. top perf. (3448')

Filled 5 1/2 csg W/sd (3761-3400') dumped 4 sk cem W/dump bailer. (3400'-3370')

Cutoff & recovered 2800' of 5 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water -

followed with 50 sk 50-50 poz 2% -displaced with 8 sk gel & water & capped with

25 sk 50-50 poz 2% & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red Mezey  
Well Plugging Supervisor

DATE 10-4-78  
INV. NO. 8213-6