

15-163-03297-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT - 2 1978  
10-02-78  
CONSERVATION DIVISION  
Wichita, Kansas  
(of this well)

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - -

Operator's Full Name Sohio Petroleum Co.

Complete Address Box 673, Russell, Kansas 67665

Lease Name Sutor "A" Well No. 9

Location NE SE SE Sec. 13 Twp. 10 Rge.      (E)      (W) 20

County Rooks Total Depth 3758'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 10:30 A Day 30 Month 9 Year 1978

The above well was plugged as follows:

Total Depth 3758' ~~885/8~~ csg set 322' cwc 200 sk.

5 1/2 csg set 3756' cw 150 sk cem. with top perf. 3448'

5 1/2 csg squeezed (890'-1014') with 331 sk cem. ~~No wire recovered.~~ Cutoff & recov. 411' of

Filled 5 1/2 csg with sand (3758'-3400') dumped 5 sk cem W/dump bailer. <sup>5 1/2 csg.</sup> (3400'-3370')

Mixed & pumped down 8 5/8 csg with 50 sk 50-50 poz 2% -displaced with 10 sk gel &

water W/200 lbs hulls, & capped with cementing plug & 70 sk 50-50 poz 2% & shutin.

FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Massey  
Well Plugging Supervisor

DATE 10-4-78  
INV. NO. 8211 W