

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW SW SE

SEC. 13 TWP. 10 RGE. 20

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 4-A ~~4-1A~~ Base Sutor

Operator Sohio ^{Petroleum} Co Address Box 673 Russell, Kans

Field _____ County Rooks

Total Depth 3734 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1605' circulated with 750 sax cement - 5 1/2" at 3730'

with 150 sax cement behind - P.B. to 3586', perforated at 3459',

Filled with sand to 3440', set 4 sax cement with dump bailer,

pulled 2885' 5 1/2" - filled with rotary mud to 300', set rock and

15 sax cement, mud to 35', set rock and 10 sax cement to bottom

cellar.

RECEIVED
STATE CORPORATION COMMISSION
PLUGGING
FILE DEC 13 T10 R20W
BOOK PAGE 125 LINE 21
12-26-56
DEC 26 1956
CONSERVATION DIVISION
WICHITA, KANSAS

District Conservation Agent

Date 12-23-56