

15-163-03334-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
9-25-78
SEP 25 1978

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

CONSERVATION DIVISION
(of Wichita, Kansas)

Operator's Full Name Sohio Petroleum Co.

Complete Address Box 673, Russell, Kansas 67665

Lease Name Sohio "A" Well No. 5X

Location NE NE SE Sec. 13 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3760'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11:25 A Day 20 Month 9 Year 1978

The above well was plugged as follows:

Total Depth 3760' 8 5/8 csg set 1635' cwc 800 sk.

5 1/2 csg set 3759' cw 150 sk cem.

Set 5 1/2 wood plug at 3300' -poured 100' sd- dumped 5 sk cem W/dump bailer. (to 3160')

Cutoff & recovered 2803' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg with 20 sk gel & water -followed with 8 5/8 plug &

50 sk 50-50 poz 2% -displaced with 8 sk gel & water & capped with 25 sk 50-50 poz 2%

& shutin.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-26-78

INV. NO. 8163-W

Signed: [Signature]
Well Plugging Supervisor