

15-163-03536-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - -

OCT - 2 1978  
10-02-78  
(of CONSERVATION DIVISION  
Wichita, Kansas)

Operator's Full Name Sohio Petroleum Co.

Complete Address Box 673, Russell, Kansas 67665

Lease Name Sutor "A" Well No. 8

Location NE NW SE Sec. 13 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3751'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 2:50 P Day 30 Month 9 Year 1978

The above well was plugged as follows:

Total Depth 3751' 8 5/8 csg set 1616' cwc 800 sk.

5 1/2 csg set 3719' cw 150 sk cem.

5 1/2 csg PBTD 3740' with top perf. (3448')

Filled 5 1/2 csg W/sd (3675'-3400') dumped 4 sk cem W/dump bailer. (3400'-3370')

Cutoff & recovered 2817' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg with 20 sk gel & water- folowed with 50 sk 50-50 poz

2% displaced with 8 sk gel & water & capped with 25 sk 50-50 poz 2% & shutin.

FPP 500 lns.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 10-4-78

INV. NO. 8215-W