

15-163-03298-0000  
P

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT - 2 1978  
10-02-78  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Sohio Petroleum Co.

Complete Address Box 673, Russell, Kansas 67665

Lease Name Sutor "A" Well No. 10

Location SW NE SE Sec. 13 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3771'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 1:40 P Day 30 Month 9 Year 1978

The above well was plugged as follows:

Total Depth 3771' 8 5/8 csg set 302' cwc 200 sk.

5 1/2 csg set 3766' cw 150 sk cem.

Dakato Leak 1084'- set BP 3500'.

Cutoff & recovered 821' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg with 50 sk 50-50 poz 2% -displaced with 15 sk gel & water W

W/300 lbs hulls, capped with cementing plug & 70 sk 50-50 poz 2% & shutin. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. E. F. Marsedy  
Well Plugging Supervisor

DATE 10-4-78  
INV. NO. 8214-W