



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE SW

SEC. 13 TWP. 10 RGE. 20 *W*

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease _____ Sutor _____

Operator Glenn Nye Drg Co ^{R.} Address Hays, Kans

Field _____ County Rooks

Total Depth 3755 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 281 circulated with cement - 5 1/2" at 3743' with
100 sax cement behind.

Filled with sand to 3735', set 4 sax cement with dump bailer,
pulled 850' 5 1/2", filled with mud to 280', set rock and 15 sax
cement, mud to 35', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 13 T 10 R 20
BOOK PAGE 26 LINE 44

RECEIVED
2-2-53

Edwin J. Kelly
District Conservation Agent

Date 1920 1-29-53